

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2020-21/OW/WORK_INDENT41784

APPROVED SCHEDULE - B

E/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Item of Work: Improvements to Roads and Drains at G Krishna Murty Layout Mutturayaswamy Layout K Muniyappa Garden in Ward No 10 Doddabommasandra Vidyanarayapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				Abbu Sambasiva Reddy ()	
				In Figures	In Words
1	247.13	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202(P.No.140- I.No.18.47) & Pg No.136, Item No.17.4,17.1	Cum	500.0	Rupees Five Hundred Only
2	185.35	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specification No.301Loading and unloading with 10km lead= (I No-19.14,P No-143)	Cum	56.0	Rupees Fifty Six Only
3	185.35	KSRB 4-1.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2	Cum	3500.0	Rupees Three Thousand Five Hundred Only
4	185.35	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, using a grade concrete M30 over a prepared base with OPC coarse aggregate @ 0.69cum fine aggregate @ 0.46cum,coarse and fine aggregate confirming to IS:383-2016,with superplastisiser @3lts confirming to IS9103-2008mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rammers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine,and curing including cost of all materials,labour,hire chargedof machines,all lead and lift charges etc., complete as per specifications. - do with OPC at 360Kg	Cum	5500.0	Rupees Five Thousand Five Hundred Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92


16/07